



# CONSTRUCTION EQUIPMENT

646559 VOLVO L260 1370 - DIESEL ENGINE



**Sample No:** VCP434926  
**Oil Type:** VOLVO ULTRA DIESEL ENGINE OIL 15W40 VDS-3  
**Job No:** 646559



## SAMPLE INFORMATION

Sample Number	VCP434926	---	---	---
Sample Date	14 Dec 2023	---	---	---
Machine Hours	512	---	---	---
Oil Hours	512	---	---	---
Oil Changed	Changed	---	---	---
Sample Status	ATTENTION	---	---	---

**FERROUS PROCESSING AND TRADING**  
 3400 E LAFAYETTE  
 DETROIT, MI  
 US 48207  
 Contact: KEITH HALL  
 keith.hall@fpt1.com  
 T:  
 F:



## OIL CONDITION

Visc @ 100°C	cSt	▲ 11.5	---	---	---
Base Number (BN)	mg KOH/g	■ 5.5	---	---	---
Oxidation (PA)	%	59	---	---	---

## Diagnosis

Oil and filter change at the time of sampling has been noted. No corrective action is recommended at this time. Resample at the next service interval to monitor. Metal levels are typical for a new component breaking in. Tests indicate that there is no fuel present in the oil. There is no indication of any contamination in the oil. The oil viscosity is lower than normal. The BN result indicates that there is suitable alkalinity remaining in the oil. Confirm oil type.



## CONTAMINATION

Water	%	NEG	---	---	---
Soot %	%	■ 0.2	---	---	---
Nitration (PA)	%	76	---	---	---
Sulfation (PA)	%	53	---	---	---
Glycol	%	NEG	---	---	---
Fuel	%	■ 0.4	---	---	---
Silicon	ppm	■ 20	---	---	---
Sodium	ppm	■ 3	---	---	---
Potassium	ppm	■ 5	---	---	---



## WEAR METALS

Iron	ppm	■ 10	---	---	---
Copper	ppm	■ 182	---	---	---
Lead	ppm	■ 0	---	---	---
Tin	ppm	■ 2	---	---	---
Aluminum	ppm	■ 3	---	---	---
Chromium	ppm	■ 0	---	---	---
Molybdenum	ppm	■ 77	---	---	---
Nickel	ppm	■ 1	---	---	---
Titanium	ppm	0	---	---	---
Silver	ppm	■ 0	---	---	---
Manganese	ppm	■ 2	---	---	---
Vanadium	ppm	< 1	---	---	---



## ADDITIVES

Calcium	ppm	■ 2000	---	---	---
Magnesium	ppm	45	---	---	---
Zinc	ppm	■ 1196	---	---	---
Phosphorus	ppm	■ 1023	---	---	---
Barium	ppm	■ < 1	---	---	---
Boron	ppm	■ 75	---	---	---

**Depot:** FERDET  
**Unique No:** 10794188  
**Signed:** Sean Felton  
**Report Date:** 22 Dec 2023



# CONSTRUCTION EQUIPMENT



## GRAPHS

