



CONSTRUCTION EQUIPMENT

702216 RENTAL VOLVO A30G 753623 - DIESEL ENGINE



Sample No: VCP446159
Oil Type: VOLVO ULTRA DIESEL ENGINE OIL 15W40 VDS-3
Job No: 702216 RENTAL



ALTA EQUIPMENT/FLAGLER CONSTRUCTION EQUIPMENT LLC
 8418 PALM RIVER ROAD
 TAMPA, FL
 US 33619
 Contact: KENNY HANEY
 khaney@flaglerce.com
 T: (813)630-0077
 F: (813)630-2233



SAMPLE INFORMATION

Sample Number	VCP446159	---	---	---
Sample Date	17 Apr 2024	---	---	---
Machine Hours	749	---	---	---
Oil Hours	0	---	---	---
Oil Changed	Changed	---	---	---
Sample Status	ABNORMAL	---	---	---



OIL CONDITION

Visc @ 100°C	cSt	● 11.3	---	---	---
Base Number (BN)	mg KOH/g	■ 5.1	---	---	---
Oxidation (PA)	%	■ 61	---	---	---



CONTAMINATION

Water	%	NEG	---	---	---
Soot %	%	■ 0.3	---	---	---
Nitration (PA)	%	■ 79	---	---	---
Sulfation (PA)	%	■ 59	---	---	---
Glycol	%	NEG	---	---	---
Fuel	%	■ 0.3	---	---	---
Silicon	ppm	▲ 35	---	---	---
Sodium	ppm	■ 4	---	---	---
Potassium	ppm	■ 2	---	---	---



WEAR METALS

Iron	ppm	■ 26	---	---	---
Copper	ppm	■ 256	---	---	---
Lead	ppm	■ 3	---	---	---
Tin	ppm	■ 2	---	---	---
Aluminum	ppm	■ 2	---	---	---
Chromium	ppm	■ <1	---	---	---
Molybdenum	ppm	■ 70	---	---	---
Nickel	ppm	■ 2	---	---	---
Titanium	ppm	<1	---	---	---
Silver	ppm	■ <1	---	---	---
Manganese	ppm	■ 4	---	---	---
Vanadium	ppm	<1	---	---	---



ADDITIVES

Calcium	ppm	■ 2216	---	---	---
Magnesium	ppm	■ 25	---	---	---
Zinc	ppm	■ 1039	---	---	---
Phosphorus	ppm	■ 910	---	---	---
Barium	ppm	■ 0	---	---	---
Boron	ppm	■ 8	---	---	---

Diagnosis

Oil and filter change at the time of sampling has been noted. No corrective action is recommended at this time. Resample at the next service interval to monitor. All component wear rates are normal. Fuel content negligible. Elemental level of silicon (Si) above normal indicating ingress of seal material. The oil viscosity is lower than normal. The BN result indicates that there is suitable alkalinity remaining in the oil. Confirm oil type.

Depot: VOLVO0093
Unique No: 10990943
Signed: Don Baldrige
Report Date: 25 Apr 2024



CONSTRUCTION EQUIPMENT



GRAPHS

